

Section 01110

SUMMARY OF WORK

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Summary of the Work including work by the City, City-furnished Products, work sequence, future work, Contractor use of Premises, special conditions for substantial completion and City occupancy.

1.02 WORK COVERED BY CONTRACT DOCUMENTS

- A. Work of the Contract is for demolition and construction of new concrete paving, curbs, landscaping, grading of detention area, new oil/water separator and electrical service to relocated electrical pole mounted light.

1.03 CASH ALLOWANCES

- A. Include the following specific Cash Allowances in Contract Price under provision of General Conditions Paragraph 3.11:

1.04 ALTERNATES

- A. From the following list of Alternates, include cost in Contract Price for only those Alternates accepted by the City and listed in the fully executed Document 00520 – Agreement, Paragraph 3.2:

1.05 CITY-FURNISHED PRODUCTS

- A. Items Furnished by the City for Installation and final connection by Contractor:
Water meter.

- B. Contractor's Responsibilities:

1. Arrange and pay for Product delivery to the site.
2. Receive and unload Products at the site; jointly with the City, inspect for completeness or damage.
3. Handle, store, Install, and finish Products.
4. Repair or replace damaged items.

1.06 WORK SEQUENCE

- A. Construct the Work in Phases during the construction period, coordinate construction schedule and operations with the City:
 1. Phase 1: No Phases.
- B. For projects with no Phases, do not disturb more than 50% of total project linear feet of disturbed right-of-way and easement until site restored in accordance with Section 01740 – Site Restoration.

SUMMARY OF WORK

C. Coordination of the Work: Refer to Section 01312 - Coordination and Meetings.

1.07 CONTRACTOR USE OF PREMISES

- A. Comply with procedures for access to the site and Contractor's use of rights-of-way as specified in Section 01145 - Use of Premises.
- B. Construction Operations: Limited to the City's rights-of-way provided by the City and areas shown or described in the Contract documents.
- C. Utility Outages and Shutdown: Provide a minimum of 48 hours notice to the City and private utility companies (when applicable), excluding weekends and holidays, in advance of required utility shutdown. Coordinate all work as required.

1.08 STREET CUT ORDINANCE

- A. Excavations on or under pavement in the City's right-of-way must have a permit. Comply with City of Houston, Texas Ordinance No. 2000-1115, an ordinance amending Chapter 40 of the Code of Ordinances, Houston, Texas, relating to excavating in the Public right-of-way.
- B. Comply with the latest edition of street cut New Pavement Repair and Pavement Replacement details.
- C. Quantities are included for street cut pavement repair and replacement in applicable Specification sections for Unit Price contracts.
- D. Include payment for street cut pavement repair and replacement in lump sum bid for Stipulated Price contracts.

1.09 WARRANTY

- A. Comply with warranty requirements in accordance with Document 00700 - General Conditions.

1.10 ADDITIONAL CONDITIONS FOR SUBSTANTIAL COMPLETION

- A. In addition to requirements outlined in Document 00700 – General Conditions, for Contractor to be substantially complete with the Work and call for inspection by Project Manager to confirm, the following conditions must be met or completed:
 - 1. All testing shall be completed and accepted by Project Manager.
- B. No additional condition to those described in Paragraph 1.10 may be included in Contractor's punch list.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION - Not Used

END OF SECTION

01110-2
02-09-2011